



NOTES:

1. WHERE SOIL CONDITIONS CAN NOT BE MAINTAINED AS SHOWN ABOVE, PROVIDE APPROVED METHOD OF CONSTRUCTION.
2. SHEETING WILL BE REQUIRED AS DETERMINED IN THE FIELD.
3. COMPACTION PERCENTAGES SHOWN REFER TO AASHTO T-180.
4. MECHANICAL COMPACTION NOT ALLOWED BELOW THIS LEVEL.
5. REMOVE UNSUITABLY SIZED STONES FOUND IN TRENCH TO A DEPTH OF AT LEAST SIX INCHES BELOW THE BOTTOM OF PIPE.

DATE: 08/24

DRAWN: KHA



CITY OF MARGATE, FLORIDA
DEPARTMENT OF ENVIRONMENTAL
AND ENGINEERING SERVICES

TRENCH DETAIL (UNPAVED AREAS)

G-13