



RESTORATION SPECIFICATION
SUMMARY TABLE

TYPE	MATERIAL	SPECIFICATION
TYPE I	SOD OR SEED	COMPACTED SUBGRADE (100% PER AASHTO T-99C) BAHIA OR ST. AUGUSTINE SOD TO MATCH EXISTING
TYPE II-A	ASPHALT DRIVEWAY	1-1/2" ASPHALT, 6" LIMEROCK (98% PER AASHTO T-180), COMPACTED SUBGRADE (100% PER AASHTO T-99C)
TYPE III	CONCRETE DRIVEWAY	6" CONCRETE (NO WIRE MESH) COMPACTED SUBGRADE (100% PER AASHTO T-99C)
TYPE IV	PAVERS	PROVIDE CONCRETE RESTRAIN AROUND PAVERS TO HOLD THEM IN PLACE. TO BE INSTALLED 1.5" BELOW THE PAVER BRICK INSTALLATION TO ALLOW SOD ABUTTING TO THE NEW DRIVEWAY. ENSURE SAND IS SWEEPED IN BETWEEN PAVERS TO LOCK IN PLACE. PROVIDE MINIMUM OF 1" OF BEDDING SAND FOR PAVER BRICKS. 6" LIMEROCK COMPACTED (98% PER AASHTO T-180; MIN. LBR=100) COMPACTED SUBGRADE (100% PER AASHTO T99C; MIN. LBR=40)

DATE: 08/24

DRAWN: KHA



CITY OF MARGATE, FLORIDA
DEPARTMENT OF ENVIRONMENTAL
AND ENGINEERING SERVICES

**TYPICAL SECTION
THROUGH SWALE**

G-23